BRUHAT BANGALORE MAHANGARA PALIKE

DASARAHALLI ZONE

Name of Work: Construction of Anganavadi Building @Karekallu in Bagalagunte ward no.14, T Dasarahalli sub divison (Note:-Water supply works)

					Est. Cost. Rs.			0.40	Lakhs
Sl. No.	Description of Item	Unit	No	L	B	D	Qty	Rate	Amount
1	Supplying water storage tanks made of virgin polymer (LLDPE) with two layers outer black or blue and inner white layer of approved quality and make, conforming to I.S.I./ISO/SSI specifications. **Page No. 270/ Item No. 37.58/ PWD SR 2012-13**	L							
	Basic Rate	5.75	1	1000			1000	6.10	6,095.00
	Area Weightage 6%	0.35							
	Total	**6.10**							
2	KSRB 8.6-8 : Providing and fixing on wall surface 2.0kg/sq.cm H.D.P.E rain down water pipes 110mm outer dia approved make and brand with necessary specials like shoes bends and offsets fixed with iron clamps, walls plugs, screws, including cost of materials, labour, complete as per specifications. **Page No.52/ Item No.8.19/ PWD SR 2012-13**	Mtr							
	Rain water line &Sanitary line		4	3.00	-	12.00	48.00		
	Basic Rate	440.00					**48.00**	466.40	**22387.00**
	Area Weightage 6%	26.40							
	Total	**466.40**							
3	KSRB 11-4 : Providing and fixing white vitreous china clay, water closets Orissa pattern of size 580 x 440mm with integral type footrests, 100m S or P trap, (approved make) cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications. **Page No.78/ Item No. 12.4 PWD SR 2012-13**	Pan							
			2				**2**	1569.86	**3,140.00**
	Basic Rate	1481.00							
	Area Weightage 6%	88.86							
	Total	**1569.86**							
4	KSRB 13-6.1.1: Providing and fixing in position brass bib cock of approved quality 15mm nominal bore including cost of all materials, labour and HOM of equipments with all leads complete as per specifications. Specification NO. KBS 13.2.2 / 13.3 **Page No.95/ Item No. 13.23 / PWD SR 2012-13**	Each							
			2				**2.00**	147.34	**295.00**
	Basic Rate	139.00							
	Area Weightage 6%	8.34							
	Total	**147.34**							

5	KSRB 11.11.9: Providing and fixing white vitreous china clay, surgeon type wash basin of size 660x460mm with single 15mm C.P brass pillar taps with single elbow operated levelers, C.I. /M.S. brackets, 32mm C.P. brass waste of standard pattern, painting of fitting and brackets, cutting and making good the wall and floor wherever required, including cost of materials, labour complete as per specifications. Specification No. KBS 11. **Page No.83/ Item No. 12.31 PWD SR 2012-13**	Unit							
			1				**1.00**	3142.90	**3,143.00**
	Basic Rate	2,965.00							
	Area Weightage 6%	177.90							
	Total	**3142.90**							
6	Providing and fixing Chorinated Poly Venyl Chloride (CPVC) pipes conforming to IS 15778, having thermal stability for hot and cold water supply including all CPVC plain and brass threaded fitting including fixing the pipe clamp at 10.00 meter spacing. This includes jointing of pipe and fittings with one step CPVC solvent cement and testing of joints complete. (internal work exposed on wall)**Page No.102/ Item No. 13.85.2 / PWD SR 2012-13 20mm nominal OD pipes**	m							
			38				**38.00**	127.20	**4,834.00**
	Basic Rate	120.00							
	Area Weightage 6%	7.20							
	Total	**127.20**							
7	Miscellaneous and unforessen Charges								**106.00**
							Grand Total		**40,000.00**

Rupees Forty Thousand Only

CERTIFICATE:-

The Work spot has been inspected and the work is found to be necessary
The Estimate is prepared as per the PW,P & IWTD -SR-2012-13
The Provision made in estimate are adequate and essential.
This area comes under BBMP limits.

Assistant Engineer
Ward no.14

Asst. Exe. Engineer
T. Dasarahalli Sub- Division
B.B.M.P

Executive Engineer
Dasarahalli Division
B.B.M.P. Bangalore.

AA = No: JC/DZ/AS/682/12-13 - 14/2/13
TS = No: EE/DD/TS/463/12-13 - 16/2/13

ನಂ. EE/DD/TS/769/13-14 ದಿನಾಂಕ : 04/3/2014
ರೂ. 40.000 thousand (Rupees Fourty Thousand only)
ಗಳ ಅಂದಾಜು ಪಟ್ಟಿಗೆ ತಾಂತ್ರಿಕ ಮಂಜೂರಾತಿ ನೀಡಿದೆ
4/3/14
ಕಾರ್ಯಪಾಲಕ ಅಭಿಯಂತರರು
ಬಿ.ಬಿ.ಎಂ.ಪಿ.ದಾಸರಹಳ್ಳಿ ವಿಭಾಗ
ದಾಸರಹಳ್ಳಿ ವಲಯ, ಬೆಂಗಳೂರು